



THIS DRAWING IS TO BE READ IN CONJUNCTION WITH SCHEME DRAWING NO 186.2022.200 - SCHEME SITE PLAN, 212 - SCHEME GROUND FLOOR PLAN, 203 - SCHEME SECTIONAL ELEVATIONS & 204 - SECTION INCLUDING DESIGN ACCESS STATEMENT,HERITAGE STATEMENT, ECOLOGY REPORT & EXTERNAL FINISHES DOCUMENT.



WEST ELEVATION (GARAGE)

Replace existing flat roof see no 186.2022.203 - proposed sectional elevations for details



IMPORTANT: As part of this planning submission we are seeking approval for new air source heat pumps and under floor heating throughout. This has been incorporated with the Design Access statement & a separate data sheet will be issued as part of this application.

IMPORTANT: As part of this planning submission we are seeking approval for a light reducing film to be applied to the fixed glazing in accordance with the previous planning officer recommendations. This has been incorporated with the Design Access statement & a separate data sheet will be issued as part of this application.

IMPORTANT: As part of this planning submission we are seeking approval for a Solar PV Panels. This has been incorporated with the Design Access statement & a separate data sheet will be issued as part of this application.

SURFACE WATER DRAINAGE: As part of this planning submission we have written approval from South West Water to connect into the existing drainage system. See Design and access statement & Drainage Surface Water Information for details.

NOTE

All rights described in Chapter IV of the Copyright, Design and Patents Act 1988 have been generally asserted.

All dimensions should be checked on site before carrying out any scheme proposals.

Proposed External Finishes to Dwelling:-

- Roof** - Natural Slate, Grey concrete ridge & hip tiles
- Fascias** - Anthracite Dark Grey Upvc or similar
- Barge Boards** - Anthracite Dark Grey Upvc or similar
- Downpipes** - Anthracite Dark Grey Powder Coated pressed metal Lindab
- Walls** - Painted render, Natural Local Stone
- Windows** - Anthracite Grey Powder coated aluminium, RAL NO 7016.
- Doors** - Anthracite Grey Powder coated aluminium, RAL NO 7016.

Proposed External Finishes to Garage:-

- Roof** - Grey GRP (replacement flat roof), Natural Slate, Grey concrete ridge tiles
- Solar Panels** - Solar Photovoltaic Panels. 1000 x 1686 x 90mm see separate data sheet.
- Fascias** - Anthracite Grey Upvc
- Barge Boards** - Anthracite Grey Upvc
- Downpipes** - Anthracite Dark Grey Powder Coated pressed metal Lindab
- Walls** - Painted Render
- Windows** - Anthracite Grey Powder coated aluminium, RAL NO 7016.
- Doors** - Anthracite Grey Powder coated aluminium, RAL NO 7016.


Proposed External Finishes:-

- Paths** - Concrete
- Steps** - Concrete with Natural Stone walls
- Retaining Walls** - Painted render and/or Natural stone with Natural Slate coping
- Drive/Parking** - Tarmac to remain
- Garden** - Lawn to remain
- Balcony** - Seamless toughened glass fitted in a stainless steel channel

FOR ALL EXTERNAL FINISHES SEE SEPARATE DOCUMENT THAT FORMS PART OF THIS PLANNING SUBMISSION

WEST ELEVATION (DWELLING)

Section B




First Floor Plan

SOUTH ELEVATION (DWELLING)

EAST ELEVATION (DWELLING)

new open porch see drawing no 186.2022.203 - proposed sectional elevations for details



SCHEME DRAWING FOR PLANNING PURPOSES



**SELENA
PRYCE
DESIGNS**

6 Scotts Close, Churchstow,
Kingsbridge, Devon TQ7 3RB.

Contact: 07835 517387
Email: selenapryce68@gmail.com



© Copyright

Client

Job Title

Alterations & Extension at
Galmpton,
Drawing Title

Scheme Drawing:-

First Floor Plan

Scale

1:50 @ A1 (1:100 @ A3)

Date

06 -03 -2022

Drawn by

s.p

Drg. No.

186-2022-202

Rev.